BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT18324/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Patching pot holes in main and cross roads of Bhadrappa layout, devinagara, lottegollahalli, muneshwaranagara, tatanagara, kodigehalli and surroundings areas in ward no. 8

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K R Taranath		
				In Figures		In Words
1	1036.32	Scarifying stone metal crust 50 to 100 mmthick with pick azxes along with premix carpet / surface dressing and stacking of old serviceable materials by manual means including cost of all labour charges complete as per specification	sqm	49.24	51028.40	Rupees Forty Nine and Twenty Four Paise Only
2	207.26	Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per MORTH specification NO. 406 with all leads and lifts etc., complete as directed by the Engineer-in-charge of the work.	cum	1662.54	344578.04	Rupees One Thousand Six Hundred Sixty Two and Fifty Four Paise Only
3	1036.32	Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the pot hole with bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete as per specifications, MORTH specification No. 3004.2,	sqm	359.33	372380.87	Rupees Three Hundred Fifty Nine and Thirty Three Paise Only
					767987.30	

Taranath

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

19/3/16

19/03